


1. SUBGRADE AND BASE ROCK BELOW PAVERS LOCATED IN RIGHT-OF-WAY SHALL BE COMPACTED TO 98% T-180.
2. \* DRIVEWAY WITHIN SIDEWALK LIMITS SHALL MAINTAIN MAXIMUM 2% CROSS SLOPE TO MEET ADA REQUIREMENTS.
3. \*\*SPECIAL PAVER SECTION REQUIRED. SEE DETAIL THIS SHEET.
- 4a. \*\*\* SIDEWALK THROUGH RESIDENTIAL DRIVEWAY TO BE 5-1/2" TRUE MEASURE DEPTH.
5. SEE TYPICAL DRIVEWAY DETAIL FOR ADDITIONAL REQUIREMENTS.
6. \*\*\* USE OF PAVER AT SIDEWALK CROSSING REQUIRES TOWN ENGINEERS APPROVAL.
7. USE OF 2-3/8" THICK PAVERS IN PUBLIC RIGHT-OF-WAY IS ACCEPTABLE FOR RESIDENTIAL LOTS.
8. ALTERNATIVES TO THE HEADER CURB SHALL BE DETAILED ON THE DRIVEWAY PERMIT APPLICATION.

### PAVER BRICK DRIVEWAY TYPICAL DETAIL



### \*\* SPECIAL PAVER BRICK SECTION



**TOWN OF JUPITER**  
ENGINEERING DIVISION

210 MILITARY TRAIL  
JUPITER, FLORIDA 33458  
(561) 746-5134

**RESIDENTIAL DRIVEWAY**

PAVER BRICKS IN RIGHT-OF-WAY  
DETAIL AND REQUIREMENTS

K:\Drawings\Details\2015\108 201507updates\108d - driveways.dwg

DETAIL NUMBER

**108d**

Revised 20100820