



NOTES:

1. POLY PIPE SHALL BE 2" PE3408 HDPE POLY TUBING, ASTM D-2737 FOR 200 PSI WITH PERMANENT SPECIFICATION MARKINGS. TUBING FITTINGS SHALL REQUIRE STAINLESS STEEL INSERTS.
2. TRAFFIC RATED BOXES SHALL BE REQUIRED IN ALL PAVED AREAS AND AREAS TO BE PAVED IN THE FUTURE.
3. ALL MATERIAL SHALL BE APPROVED BY THE TOWN OF JUPITER WATER UTILITIES PRIOR TO INSTALLATION.
4. ALL PIPING SHALL BE RESTRAINED PER TOWN OF JUPITER STANDARDS.
5. TRACER WIRE SHALL BE INSTALLED ON ALL NON-DUCTILE IRON WATER MAIN.
6. TRACER WIRE SHALL BE COPPERHEAD INDUSTRIES, LLC PART NUMBER 1430-HS OR APPROVED EQUAL.
7. TRACER WIRE SHALL DEAD END WITH COPPERHEAD MAGNESIUM ANODE PART NUMBER ANO-1005 OR APPROVED EQUAL.
8. ABOVE GROUND TEST STATION SHALL BE COPPERHEAD INDUSTRIES, LLC PART NUMBER T1-B75 OR APPROVED EQUAL.

TEMPORARY BLOWOFF

**JUPITER UTILITIES**  
CONSTRUCTION STANDARDS AND DETAILS

DATE APPROVED:  
06/2017  
DRAWING No. W-18B